

A table below shows mistakes and thrifths of contractors in fixing render systems

CONTRACTOR'S MISTAKE	CONTRACTOR'S THRIFT	EFFECTS	RESULTS
<i>Glueing material without an adhesive frame around</i>	Glue saving - lower price	Insulation slab loosening	All slabs are visible on the facade
<i>Instead of mesh embedding in glue surface – nailing in and covering with glue,</i>	Glue and work time saving - lower price,	Detachment of glue and render from insulat	Facade comes away
<i>Lack of corner casing reinforcement,</i>	Work time saving - lower price,	Facade cracking on long sectors,	Water penetration deep in the facade – external insulation damage,
<i>Lack of insulat slabs leveling with the sandpaper,</i>	Work time saving - lower price,	Chemical pollutants settling,	Facade damage and polution,